

Tensar's InterAx™ geogrid rolls into Ohio

The use of InterAx™ geogrid enabled construction of heavily trafficked unpaved entrance lane.



Mosser Construction Equipment Yard

📍 Fremont, OH

Mosser Construction
Owner / Contractor

Installation: March 2021
Product: NX750™

Tensar's InterAx geogrid
section was equivalent to 26"
of traditional undercut & fill

CLIENT'S CHALLENGE

Mosser Construction sought to replace the unpaved main entrance lane into their Fremont, Ohio equipment yard. The entrance road receives a high amount of heavy traffic, so long term performance is critical.

TENSAR SOLUTION

Tensar performed DCP tests to determine subgrade conditions and provide a solution that would meet the project objectives – a cost-effective section with minimal maintenance over the long term. 8" ODOT 304 aggregate over Tensar's InterAx NX750 geogrid was installed.

